



2587 C.R. 44 WEST
EUSTIS, FL. 32726
PH: 352 483-7020
www.tlpfi.com

5/16/2025

PROPOSAL & SCOPE OF WORK FOR:
Saxon WTF

This proposal is based on a Site Visit on 7/25/2023

1) PROVIDE AND INSTALL CLASS 1 EXPOSED ALUMINUM ROOF TOP LIGHTNING PROTECTION SYSTEM WITH COPPER DOWNLEAD CONDUCTORS TERMINATING AT 5/8"X20' COPPER CLAD GROUND RODS. SEE ADDER BELOW FOR CLASS 1 COPPER COUNTERPOISE FOR ALL STRUCTURES/ BUILDINGS WITH INTERCONNECTIONS BETWEEN FOR WHOLE PLANT GROUND GRID. SEE PAGE 2 FOR LIST OF BUILDINGS/ STRUCTURES INCLUDED.

2) ALL WORK TO BE IN STRICT ACCORDANCE WITH U.L. 96A, N.F.P.A. 780 & L.P.I. 175.

3) SURGE SUPPRESSION DEVICES NOT INCLUDED. NOTE: U.L. REQUIRES SPD PER UL1449 3RD ED.

4) ALL FLASHINGS & ANY SPECIAL REQUIRMENTS THAT MAY BE REQUIRED BY THE ROOFING CONTRACTOR OR ROOF MANUFACTURER TO BE SUPPLIED AND INSTALLED BY OTHERS. (IE: SACRIFICIAL PADS, PAVERS, HEATWELD STRAPPING AND ANY OTHER SPECIAL METHODS THAT MAY BE REQUIRED.)

5) ALL REQUIRED PVC CONDUIT WITH PULL STRINGS FOR DOWNLEAD CONDUCTORS TO BE SUPPLIED AND INSTALLED BY TLP. APPROX 300' REQ'D. ALL CONDUIT FOR LP MUST BE STRAPPED 3' OC PER UL 96A. PER SITE.

6) ANY REQUIRED CONCRETE AND/OR ASPHALT CUTTING OR PATCHING OR JACK & BORING THAT MAY BE REQUIRED BY OTHERS.

7) WE HAVE INCLUDED FORMAL CERTIFICATION BY UNDERWRITER'S LABORATORIES. FOR ALL ELIGIBLE STRUCTURES/ BUILDINGS.

TOTAL COST AS OUTLINED ABOVE:

LIGHTNING PROTECTION: \$33,909.00

COUNTERPOISE/ GROUND GRID: \$25,799.00

Proposal is based on providing T.L.P. Standard Insurance Coverage.

Due to the fluctuating commodities market, this Proposal is valid for 30 days.

IF YOU HAVE ANY QUESTIONS OR CONCERNS REGARDING THIS SCOPE & PROPOSAL, PLEASE FEEL FREE TO CONTACT ME.

Bobby J. Schulte
President

Bobby J. Schulte



Master Installer /
Designer
#1070 & #1483



OWAY-IE
323097



#989991



BUILDINGS/ STRUCTURES INCLUDED

1. GST #1
2. GST #2
3. HSP BUILDING
4. AMMONIA BUILDING
5. ANTENNA
6. WELL #14
7. WELL #16



Master Installer /
Designer
#1070 & #1483



OWAYE
222097



#989991