Lightning Protection

Closed

98

3

0

0

O

Broadcast to

Viewed Quotes

Submitted Quote

Not Quoting

Quoting But Later

Quote Details

Quote Number

KD2025-09

Due

Jun 17, 2025 2:00pm (EDT)

Broadcast Date

Jun 11, 2025 3:00pm (EDT)

Days to deliver after Receipt of

Order (ARO)

None

Shipping Notes

None

Additional Specifications

None

Insurance and Additional

Requirements

Terms and Conditions

Contact Name

Kate Duffy

Contact Address

City of Deltona - Purchasing and Building Services, 2345 Providence Boulevard, Deltona, FL 32725,

United States of America

Contact Email

kduffy@deltonafl.gov

Contact Phone

386-878-8100

Shipping Name

Kate Duffy

Shipping Address

City of Deltona - Purchasing and Building Services, 2345 Providence Boulevard, Deltona, FL 32725,

United States of America

Shipping Phone

386-878-8100

Documents

Filename	Туре	File Type	File Size	Date Modified	Status
Written Quote Request for Lightning Protection	Quote Document / Specifications	DOC	0.24 KB	Jun 11, 2025	Complete

Commodity Code

 $[008-203-67] \ Power \ Supplies: Surge \ Protectors, \ Uninterruptible \ Power \ Supplies, Switches, etc., \ Environmentally \ Certified \ Products$

 $[008\text{-}207\text{-}67] \ \text{Power Supplies: Surge Protectors, Uninterruptible Power Supplies, Switches, etc.} \\$

[015-220-87] Weather Instruments: Anemometers, Barographs, Barometers, Hygrometers, Lightning Strike Counters, Relative Humidity Meters, Thermographs, Radar Weather Display, etc.

[023-984-57] Power Supplies Rental or Lease: Surge Protectors, UPS, etc.

[028-285-03] Arresters, Lightning

Show More ≽

Project Name: Deltona WTP #7 Location: 1240 Saxon Blvd

SCOPE:

- 1) Includes protecting 2 storage tanks, 2 buildings, and pump enclosure with an exposed class I lightning system.
- 2) Aluminum roof system/materials
- 3) Copper exposed downleads
- 4) 5/8"x 20' ground rods. Each downlead will terminate to a single 20ft ground rod.
- 5) Includes adding antenna grounding and revising the existing connection components.
- 6) providing design & installation in compliance with NFPA 780, UL96A, and LPI 175 lightning protection standards requirements.
- 7) Includes a third-party certification, obtained through LPI IP Master inspection/certification program.
- 8) Based on work performed utilizing a ladder. Excludes scaffolding or man lift costs.
- 9) Includes 1 site assessment meeting to finalize design requirements.

Furnished & Installed .

- GST #1 (80ft diameter) Lightning Protection System

 The non-conventional (non-code compliant) ESE Mast can be removed or remain in place and interconnected with the new code compliant LP system.
- GST #2 (70ft diameter) Lightning Protection System
- Building 1 (260ft perimeter) Lightning Protection System
- Building 2 (60ft perimeter) Lightning Protection System
- 2 Pump Enclosure (36ft perimeter) Lightning Protection system. Includes bonding to pump.
- Antenna Grounding