



Proposal #: 032924-1R

Date: 3/29/2024

Submitted to: Jeff

Company: City of Deltona

Email: jelder@deltonafl.gov

2320 Beardall Ave, Sanford, FL 32771 P.O. BOX 291671-32129 (386) 882-6200

State License #CUC 1224744

Job Description: 36" Main Repair / Beaver Ct Well (City of Deltona)

We are pleased to quote labor & materials to include:

- Cut concrete driveway & dispose of removed materials.
- Excavate 36" DI pipe water main.
- Cut & remove existing (2) 1" SCH-80 pipe for chlorine feed over the 36" pipe.
- Cut & Remove existing (2) 3" SCH-80 pipe chase over 36" pipe.
- Provide trench box for excavation over 4ft deep.
- Cut 36" main and remove leaking MJ connection.
- Furnish & Install (1) 36" MJ Long Sleeve with mega lug restraints.
- Furnish & Install (1) 36" MJ mega lug restraint at existing MJ connection.
- Furnish & Install (2) 1" SCH-80 PVC pipe & couplings to reconnect chlorine feed line.
- Furnish & Install (2) 3" SCH-80 PVC pipe & couplings to reconnect chase pipes.
- Backfill & Compact excavated area.
- Furnish & Install 6ft x 12ft x 6" concrete driveway.
- Restoration of site when complete.

TOTAL: \$42,385.00

NOTE: Ground water in this location is extremely high and may require several days to dry up area enough for it to be excavated.

Terms Net 30 Days

All material is guaranteed to be as specified. All work to be completed in a workmanlike manner according to standard practices. Any alteration or deviation from above specifications involving extra cost will be executed only upon written orders and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control. This proposal is subject to acceptance within 30 days and is void thereafter at the option of the undersigned.

Authorized Signature:

Raymond Rogers
(386) 882-6200
raymond@danusutilities.com